

Dear Customer,

Welcome to LG Electronics. We appreciate your decision and thank you for purchasing the Split Air conditioner from India's leading Air conditioner brand.

We, at LG recommend our customers to get the air-conditioner installed through our authorized service centre only.

BEFORE YOU PAY FOR THE INSTALLATION

- We request you to kindly get the below mentioned points re-verified.
- Verification will assure that you get uninterrupted desired performance throughout the year.

Check for gas leak

- Kindly cross verify that both indoor and outdoor side nuts are checked for gas leak with soap solution by installer. If bubbles seen, means gas leak.


If any leak in these area, ask installer to repair the same.



Check for water leak

- Ask concerned to open inlet grill.
- Ask installer to put about 3 litre water slowly. No water should fall inside the room.


If water falls ask him to repair the same immediately.



Wiring connection check

- Wiring connection should not be loose.
- Loose wiring can cause electric shock / fire / damage to product or personal.

If any wiring found loose, ask installer to repair the same.



Main wiring
(Plug / MCB
area)

Filter Cleaning Process

- Filter should be cleaned every fortnight (in 15 days, of running time).
- Ask installer to show how to remove and clean filter.
- If filter is not cleaned it can cause low cooling / noise, other issues.
- Filter cleaning is preventive maintenance.



Machine running

- Once the installation is complete, ask installer person to run machine for **minimum 15 minutes**.
- Ask him to verify the **temperature difference using thermometer**.
- Ask installer to give proper **DEMONSTRATION** of product.
- No installation is complete till air conditioner is checked for all functions.

प्रिय ग्राहक,

LG Electronics में आपका स्वागत है। हम आपके निर्णय की प्रशंसा करते हैं तथा भारत के उत्तम एअर कण्डीशनर ब्राण्ड्स का स्प्लिट एअर कण्डीशनर खरीदने के लिए धन्यवाद देते हैं।


LG अपने ग्राहकों को केवल अधिकृत सर्विस सैन्टर के माध्यम से ही एअर कण्डीशनर लगवाने की सलाह देते हैं।

इंस्टॉलेशन का भुगतान करने से पहले

- कृपया आप निम्नलिखित निर्देश बिन्दुओं की पुनः जाँच कर लें।
- जाँच करने से आपको विश्वास हो जायेगा कि आपको बिना किसी रुकावट के पूरे वर्ष मनचाही कार्य प्रणाली मिलेगी।


गैस रिसने की जाँच

- अन्दर एवं बाहर लगे नट के जोड़ चेक करवाएं।
- चेक करने के लिए साबुन के घोल का उपयोग करना चाहिए।
- अगर साबुन के बुलबुले दिखें तो इंस्टॉलर को सही करने के लिए कहें।




पानी रिसने की जाँच

- इंस्टॉलर को ग्रिल खोलने के लिए कहें।
- उसके बाद करीब 3 लीटर पानी डालने के लिए कहें, पानी कमरे में नहीं आना चाहिए।
- अगर पानी कमरे में गिरे तो इंस्टॉलर को सही करने के लिए कहें।



बिजली कनेक्शन की जाँच


- बिजली का कनेक्शन ढीला न हो।
- ढीले या गलत कनेक्शन से झटका / आग या मशीन में समस्या आ सकती है।
- अगर कनेक्शन ढीला / गलत मिले तो उसे सही करवायें।



Main wiring
(Plug / MCB
area)

फिल्टर साफ करने का तरीका

- इंस्टॉलर को ग्रिल खोल कर फिल्टर निकालकर दिखाने के लिए कहें।
- हर 15 दिन में फिल्टर साफ करना चाहिए।
- यह कार्य करने से ए सी ठीक से ठंडा करता रहता है।



मशीन का चलना

- इंस्टॉलेशन खत्म होने के बाद इंस्टॉलर को मशीन चालू करने को कहें।
- मशीन को कम से कम 15 मिनट तक चलाएं, उसके बाद इंस्टॉलर से तापमान चेक करवाएं।
- इंस्टॉलर को मशीन की सभी डिटेल्स समझाने को कहें। उसके उपरान्त ही पैसे का भुगतान करें।